Cabinet of Ministers

Egyptian Environmental Affairs Agency

Egyptian Pollution Abatement Project (PMU)

رئاســة مجلـس الوزراء جهـاز شئون البيئـة

وحدة تنفيذ مشروع مكافحة التلوث (المرجلة الثانية)

Case Summary

Abu- Zaabal Company for Fertilizers And Chemical Industries

Company Information:

Contact Person: Eng /Moastafa El Gabali

Position: Executive Director

Telephone: 012-7379858 02-44620082 02-44620682

Fax: 02-44621931 Sector: Private Number of labors: 1600

Project Title: Rehabilitation of Phosphoric acid plant.

Type of Project: Air Pollution & work environment control, Water recycling

1. **Basic Information**

1.1 Main Products

Products	Actual Average Production, t/y
Powdered and granulated Single Super Phosphate (17% P ₂ O ₅)	585,000
Granulated Triple Super Phosphate (48% P ₂ O ₅)	87,000
Sulfuric acid	300,000 (used in production)
Phosphoric acid (48-50% P ₂ O ₅)	41,000 (34,800 used in TSP production)

1.2 Raw Materials & Utilities

Raw materials		Current Consumption, t/y	
Phosphate Ore (24	-30% P ₂ O ₅)	628,000	
Sulfur		100,000	
Utilities	Usage	Consumption, m3/y	Source
Water	Total	4,500,000	Ismailia Canal
	Туре	Consumption /y	
Fuel	Natural gas, m3/y	15,000,000	
	Source	Consumption, MWh/y	
Electricity	Self Generated Electricity		25,000
	Grid Electricity		25,000
Products		Actual Average Production, t/y	
Powdered and granulated Single Super Phosphate (17% P ₂ O ₅)		585,000	
Granulated Triple Super Phosphate (48% P ₂ O ₅)		87,000	
Sulfuric acid		300,000 (used in production)	
Phosphoric acid (48-50% P ₂ O ₅)		41,000 (34,800 used in TSP production)	

1.3 Project Location:

El Maahd road – Abu Zaabal – Qulubia Governorate

1.4 Project Objectives:

- Reduction of Hydrogen fluoride (HF) and dust in work Place, to reach Compliance with Egyptian Environmental law.
- Eliminate Cooling Ponds.

1.5 Project Description:

Rehabilitation of phosphoric acid production units to increasing the line efficiency and achieve design capacity. Modifications include filter, agitators and scrubbers, heat exchanger, pumps

Abu Zaabal Company has an old belt weigher. This weigher is in bad condition causing a huge load of dust pollution. The company needs to replace it with a new one in the phosphate grinding plant. This project is part of rehabilitation of the phosphoric acid plant.

AZFC is requesting the purchase cooling tower to minimize contamination of water table by P_2O_5 caused by discharging cooling water in a cooling pond.

Abu Zaabal Fertilizer & Chemical Co. will revamping its existing Lupolco mills which is part of Phosphoric acid plant through EPAP II. The revamp of the three mills will drastically minimize dust emissions at the plant to standard acceptable dust level emissions using distributed control system (DCS) to monitor productivity and emissions standards and bring their productivity to original design., Rehabilitation of bag filter & feeding system

A pneumatic conveying system will be installed to transport phosphate rock from the three mills to Silo 241. Air emissions in this area are expected to be reduced to the law limits.

1.6 Project Components:

- 1) Filter, Agitators, Scrubber, Spare Parts
- 2) Belt conveyor
- 3) Cooling Tower
- 4) Heat exchanger
- 5) Pumps
- 6) Roll Feeder , Classifier , Grinding Table, Mill Liner , Gear box
- 7) Feeding, Control system, Bag Filters
- 8) Pneumatic Conveyers

1.7 Actual Project Cost:

Total project cost for the 8 components is \$ 9.330 M of which MUS\$ 8.291 are financed from EPAPII

Component 1: Total cost MUS\$ 5.468 M of which MUS\$ 4.971 are financed from EPAPII for (Filter, Agitator, Scrubber, and Spare Parts).

Component 2 :Total cost for Belt weigher US\$ 0.119 M with US\$ 0.116 M Financed from EPAPII

Component 3: Total cost for cooling Tower US\$ 0.403 M with US\$ \$ 0.391 M Financed from EPAPII

Component 4 : Total cost for Heat exchanger is MUS\$ 0.223 of which MUS\$ 0.193 are financed from EPAPII

Component 5: Total cost for Pumps is MUS\$ 0.484 of which MUS\$ 0.435are financed from EPAPII

Component 6:Total cost for the first part, rehabilitation of Lupolco mills, US\$ 0.858 M with US\$ 0.752M Financed from EPAPII

Component 7 :Total cost for rehabilitation of feeding & de-dusting and control system for Lupolco mills, US\$ 1.511 M with US\$ 1.172 M financed from EPAPII

Component 8 :Total cost for Pneumatic Conveyers US\$ 0.264 M with US\$ 0.261 M Financed from EPAPII

1.8 EPAP Technical Support:

The PMU assisted Abu Zaabal Company in auditing, bidding and any technical data needs.

EPAP II TA has prepared the Audit and compliance action plan (CAP) EPAP II PMU assisted the company in preparing:

- Tender document.
- The bid evaluation report and procurement procedures.
- Contract between the company & the bidder.

2. Eligibility Criteria

2.1 Environmental

- 1) The Project will reduce Dust and HF emissions
- 2) The Project will improve the environmental conditions by eliminating soil contamination with P2O5 which is currently occurring due to the usage of a cooling pond.

Load reduction

Sub-project Components	Target pollutant	Load reduction
Rehabilitation of process units	HF in workplace	42%
Installation of heat exchanger	HF in stack emissions	6.83 t/y
	Scrubber waste water	100%
	Fluorosilisic acid and P2O5 in	50%
	phosphogypsum	
Installation of cooling tower	Amount of cooling water to	100%
	pond	
Revamping of Lopulco mills	Dust in workplace at Lopulco	TSP 56%, PM10
Replacement of belt weigher	mills	90%
Installation of control system and bag		
filters for Lopulco mills		
Pneumatic conveying system for	Dust in workplace	50%
phosphate rock		

2.2 Financial:

Payback Period is 1.06 years

3. Current status of project procedures

3.1 Steering committee approval: approved3.2 Co-financers approval: approved

Item	No Objection
Comp 1:Rehabilitation of phosphoric acid	January 2007
production units(filter, agitators and scrubbers)	
Direct contracting	
Comp 6: Rehabilitation of Lupolco mills	Oct 2007
Direct contracting	

3.3 Technical Procedures:

Technical Document	submitted	Approved	Date
Environmental	Y	Y	Aug 2009
Assessment			
Compliance Action	Y	Y	Aug 2009
Plan (CAP)			-
Environmental Impact	Y	Y	Feb 2009
Assessment (EIA)			
Technical Agreement	Y	Y	Jan 2009

3.4 Implementation Procedures:

3.4.1 Procurement Procedures:

The Procurement Procedure were followed for the 8 component

- 1. With respect to the implementation of the project, The Company asked for a "Direct Contracting" to Profile Company for these Items (Filter, Agitators, Scrubber, Spare Parts) because Profile Co. is the only company in the world which has the patent for these parts.
- 2. AZFC requested for "shopping" method for purchasing the Belt Wires
- 3. AZFC requested for "shopping" method for purchasing the Cooling Tower.
- 4. AZFC Used "shopping" method for purchasing the Heat exchanger
- 5. AZFC Used "shopping" method for purchasing the Pumps
- 6. The company asked for a "Direct Contracting" to Metso Co.to revamping Lupolco mills and that supplies original spare parts for Lupolco mills, because Lupolco Co. has ceased to exist and therefore cannot do the refurbishing of the mills. Metso Co. is the only specialized company in the world that is dedicated to revamping Lupolco mills and that supplies original spare parts for Lupolco mills.
- 7. The company followed proposed EPAPII single stage model for rehabilitation of feeding & de-dusting and control system for Lupolco mills.
- 8. AZFC requested for "shopping" method for purchasing the Pneumatic Conveying

3.4.2 Status of Implementation:

		Date	
Technical Document	submitted	Achieved	Planned
Credit worthiness certificate	Y	Feb 07	
Sub-loan Agreement	Y		
Bidding Document(B.D)/	Y	Comp 2: 17/8/07(I.L)	
Invitation letter (IL)		Comp 3: 16/7/ 07(IL)	
		Comp 4: 1/12/2007(IL)	
		Comp 5:25/12/2007(IL)	
		Comp 7 : 26/6/08(B.D)	
		Comp 8 : 15/1/09(IL)	
Technical and financial	Y	Comp 2: 31/10/07	
Evaluation		Comp 3: 15/9/07	
		Comp 4: 30/12/08	
		Comp 5:2/8/2008	
		Comp 6: 18/7/08	
		Comp 7: 5/4/09	
Awarding and Contracting	Y	Comp 1: 25/1/07	
		Comp 2: 4/11/07	
		Comp 3: 5/11/07	

		Comp 4: 20/1/08	
		Comp 5:3/3/2008	
		Comp 6: Feb. 08	
		Comp 7:28/8/08	
		Comp 8: 14/4/09	
Installation and	Y	Dec 2011	Sep 2011
Commissioning			
Monitoring:	Y	Apr 2012	Dec 2011
Q1:			Dec 2011
Q2:	Y	July 2012	Mar 2012
Q3:	Y	Dec 2012	Jun 2012
Q4:	Y	Mar 2013	Sep 2012