Cabinet of Ministers

Egyptian Environmental Affairs Agency

Egyptian Pollution Abatement

Project(EPAPII)

رئاسة مجلس الوزراء جهاز شئون البيئة مشروع مكافحة التلوث (المرحلة الثانية)

Case Summary

Suez Cement Group Helwan Cement Company

Company Information:

Contact Person: Eng.Mohamed Ayman

Position: Corporate Environment Manager

Telephone: 2522 2029 Fax: 25010428

Email: m.aymen@suezcem.com

Sector: Private

Project Title: Replacement/upgrading of existing EPs to Bag Filters,

Covering cement mills 1,3,4,5 feeding points and

Installion of Continuous emission monitoring system for

NOx & SOx

Type of Project: Air pollution control and Work placement reduction

1. Basic Information:

1.1 **Main Product:**

Product	Ton/year
Clinker (Intermediate)	3328000
Cement	4240531

1.2 **Raw Material**:

Raw Materials:		
Limestone	4893180 t/y	
Clay	1606320 t/y	
Pyrite	30136 t/y	
Gypsum	396378 t/y	
Energy:		
Mazot	180456 t/y	
Natural Gas	208389000 m3/y	
Electricity:		
From outside grid	504961155 kwh	
Water:		
Municipal	2520000 m3/year	

1.3 **Project Location**:

Kafr El-Elwa near nile river – Helwan Governorate, P.O.Box 16, Cairo, EGYPT

1.4 **Project Objectives:**

- Reduction of TSP in stack emissions from an average of 700 t/y to <100 t/y.
- Reduction of TSP and PM₁₀ emissions in workplace to comply with the Environmental law 4/1994 modified by law 9/2009 and other environmental regulations.
- Emission load before and after implementation the project will be:

Parameters	Before the project	After the project	Reduction %
	(t/y)	(t/y)	
Dust	733	121	83.5%

1.5 **Project Description:**

The sub-project consists of the following:

	Plant	Project description	Estimated cost KEGP
	Plants 1,2,3	Vacuum cleaning truck	1146
		Cover CM 1, 3, 4, 5 bankers & install 4 new bag filters	880
		New bag filter for packing M/C 3	600
		New bag filter for kiln feed system line 2	446
		New bag filter for cement mill 3 plant 2	540
	Cement mill 4 EP conversion	600	
		Cement mill 5 EP conversion	600
Helwan Plant 2	Cement mill6 EP conversion	1000	
	Cement mill 7 EP conversion	1000	
	Plant 2	Cement mill 8 EP conversion	872
		Cement mill 9 EP conversion	950
		Upgrading the exists compressed air	800
		station to cover the needed compressed	
		air capacities for the bag filters	
		One device continues emission monitoring	1800
	for Sox & Nox		
		One device continues emission monitoring for Sox & Nox	1800
		TOTAL	13,034 = US \$ 2.4 M

1.6 **Project Components:**

- Vacuum cleaning truck to enhance work environment
- Covers for CM 1,3,4,5 bankers and 4 bag filters
- Conversion of existing EPs to Bag filters for 6 cement mills
- 1 bag filter for packing machine no.3
- 1 bag filter for kiln feed of line 2
- 1 bag filter for cement mill 3 in Plant 2
- 2 continuous emission monitoring devices for SOx & NOx

1.7 Actual Project Cost:

Total project cost US\$ 2.64 M with US\$ 2.4 M Financed from EPAPII

1.8 **EPAP Technical Support:**

EPAP II TA prepared:

- Environmental audit(Part II)
- Compliance Action Plane (CAP)

EPAP II PMU will prepare:

• Technical agreement

2. Eligibility Criteria

2.1 **Environmental:**

- Emission load reduction by 83%
- Move from non-compliance to compliance

2.2 Financial:

- The project costs less than US\$ 8 million
- For cement mills bag filters with capital investment US\$ 1000000 and assuming cement losses 0.01% to be recycled back, payback period is about 16 years.

3. <u>Current status of project procedures:</u>

3.1 Steering committee approval: N.A

3.2 Co-financers approval: N.A

3.3 **Technical Procedures:**

Technical Document	submitted	Approved	Date
Environmental Assessment	Y	Y	Sep 2010
Compliance Action Plan (CAP)	Y	Y	May 2010
Environmental Impact Assessment	N/A	N/A	
(EIA)			
Technical Agreement	N	N	

3.4 Implementation Procedures:

3.4.1 **Procurement procedures**:

• HCC (Helwan Cement Company) requested for "shopping" method

3.4.2 Status of Implementation:

		Date	
Technical Document	submitted		
		Achieved	Planned
Credit worthiness certificate	Y	August 2010	July 2010
Financial Agreement	N	-	October 2010
Awarding & Contracting	Y		Jan 2011
Installation and Commissioning	N		Jan2012
Startup	N		
Monitoring:	N		
Q1:	N		
Q2:	N		
Q3:	N		_
Q4:	N		